



► Equipe d'appui technique de l'OIT au travail
décent pour l'Afrique centrale et bureau de pays
de l'OIT pour le Cameroun, São Tomé- et-Principe
et Guinée équatoriale

Sir/Madam

28 March 2022

R: CMR1-4-1-0

N°166/AM/CAOL/es

Call of expression

Sir/Madam,

The International Labor Office in Yaoundé would like to acquire the equipment of the cobblestone production workshop for its HIMO ILO-MINH DU Project based in Bamenda. The generic technical requirements specifications are described in appendix 2.

Given the barrier measures related to COVID-19, we would be grateful if you could send us your offer by email to yaounde@ilo.org no later than **April 12, 2022, at 2:00 p.m. prompt.**


The subject of the e-mail must bear the sole mention **"HIMO-BIT MINH DU Project Submission Material for the production of pavements"**.

The equipment must be provided with a guarantee of at least 12 months against all manufacturing defects relating to the mechanical, electrical, and electronic components. The tenderer will have to also indicate the delivery time.

ILO reserves the right to reject your offer if it does not meet the technical specifications provided and the other requirements of this request for quotation.

The prices, to be indicated as part of the estimate in Appendix 1, must be denominated in XAF indicating explicitly in figures and in words the exact amounts excluding VAT and/or including VAT.

The acceptance of your offer will be materialized by the establishment of a purchase order in favor of your company, the delivery will be 2 weeks, as from the signature of the Purchase order, at the Office of the ILO located at the UNHCR Building, Up Station Northwest Region.


Aminata Maiga
Director



APPENDIX 1: Framework of the estimate

LOT 1: Paving stone production equipment

No.	Name	Unity	Amount	Unit Price	Total price
1.1	Vibrating table	U	3		
TOTAL AMOUNT EXCLUDING VAT					

LOT 2: Small concrete production equipment

No.	Name	Unity	Amount	Unit Price	Total price
2.1	Molds for interlocking pavements type Trieff (13 cm)	U	150		
2.2	Molds for interlocking pavements type Trieff (8 cm)	U	150		
2.3	Edging molds	U	30		
TOTAL AMOUNT EXCLUDING VAT					

LOT 3: Concrete production equipment

No.	Name	Unity	Amount	Unit Price	Total price
3.1	Cement mixer industrial	U	3		
TOTAL AMOUNT EXCLUDING VAT					

LOT 4: Implementation equipment

No.	Name	Unity	Amount	Unit Price	Total price
4.1	3-ton vibratory compactor	U	1		
TOTAL AMOUNT EXCLUDING VAT					

LOT 5: Small Implementation Equipment

No.	Name	Unity	Amount	Unit Price	Total price
5.1	Vibrating plate	U	3		
5.2	Vibrating needle	U	3		
5.3	3m3 tricycle	U	3		
TOTAL AMOUNT EXCLUDING VAT					

LOT 6: Small construction equipment and personal protective equipment

No.	Name	Unity	Amount	Unit Price	Total price
6.1	Wheelbarrow	U	30		
6.2	Shovel round	U	30		
6.3	Shovel spade	U	30		
6.4	mason 's trowel	U	30		
6.5	10 liter bucket	U	30		
6.6	1,000 liter cubicle for water reserve	U	3		
6.7	1,000 liter cubicle for diesel reserve	U	3		
6.8	Work clothes (trousers + jacket) with ILO logo	U	150		
6.9	shoe (boots)	U	150		
6.10	shoe (safety)	U	40		
6.11	work helmet	U	150		
6.12	Soft Leather Work Glove	U	150		
6.13	Stone protection bezel	U	150		
TOTAL AMOUNT EXCLUDING VAT					

APPENDIX 2: TECHNICAL DESCRIPTION OF THE LOTS

LOT 1: Pavements production Equipment

1.1 Vibrating tables

Supply and installation of vibrating tables with trays of at least 2 m² for a capacity of around twenty molds. The table must have a single or three-phase motor with an automatic cut-out system in the event of overvoltage. Voltage: 220v Weight: 500kg, 500kg Dimension (L*W*H): 2000*1000*700, Warranty: 6 months

LOT 2: Concrete production equipment

2.1 Molds for Trieff- type interlocking Pavementss (13 cm)

2.2 Molds for Trieff- type interlocking blocks (8 cm)

2.3 Edging molds

Plastic mold.

LOT 3: Industrial concrete mixers

Supply of industrial concrete mixers of at least 500 l with a minimum 2 HP Diesel engine.

Mixing power: 7.5HP; Filling capacity: 500L; Overall Dimension:200*100*120CM; Warranty: 6 months; Productivity: 18M³ /H

LOT 4: Implementation equipment

4.1 Compactor

Supply of a 3 tons compactor, preferably of the BOMAG brand Listings360 type.

Travel speed: 0-5km/h; Category capacity: 30%; Power (W): 6.0HP~32.7HP; Dimension (L*W*H):2100*1000*1650mm; Weight: 3 Tons; Warranty: 1 YEAR

LOT 5: Small implementation equipment

5.1 Tricycle

Supply of tricycles of 3 m³ minimum with An Engine of 3 HP minimum.

5.2 Vibrating plates

Supply of 3 vibrating plate types BP 18 45 DL with plate surface ≥45 cm.

5.3 Vibrating needle

Supply of 3 vibrating needles for concrete compaction.

LOT 6: Small construction equipment and personal protective equipment (PPE)

6.1 Wheelbarrows

Supply of wheelbarrows in galvanized sheet metal reinforced handles and wheel holders.

6.2 Shovel round

Supply of round shovel in galvanized sheet metal with wooden handles.

6.3 Shovel spade

Supply of straight shovel in galvanized sheet metal with wooden handles.

6.4 Trowel

Supply of masonry trowel in galvanized sheet metal with reinforced handles.

seal, etc

Supply of plastic masonry seal with cord.

6.5 1,000-liter cubicle for water reserve

6.6 1,000-liter cubicle for diesel reserve

6.7 work clothes

Supply of work clothes in different sizes in light terylene fabric with the inscription of the site logo on the back (logo sample available from the ILO).

6.8 shoes (boots)

Supply of work shoes, high-quality plastic boot type.

6.9 shoes (safety)

Supply of suede work shoes with reinforced toe caps.

6.10 Gloves

Supply of velvety leather work glove in various sizes.

6.11 Helmets

Supply of hard hats with adjustable straps.

6.12 Protective glasses

Supply of impact protection lenses with safety lanyard.